

KOLAR GOLD FIELDS.

The 19th December 1902.

1. Notice is hereby given that sealed tenders will be received at the office of the President, Sanitary Board, Kolar Gold Fields, up to Saturday the 31st January 1903, for roofing the Ooregum Shandi platforms with Mangalore tiles. The detailed estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1903.

2. The plan, detailed estimate and conditions may be seen at the office of the President, Sanitary Board, Kolar Gold Fields, between the hours of 11 A.M. and 5 P.M.

3. The tenders should be accompanied by a statement in the form given below showing the rates and the cost at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees two hundred, in currency notes only, as earnest money, and be superscribed "Tender for roofing Platforms at Ooregum Shandi enclosure" and each tender must be sent through Registered Post to the address of the Vice-President, Sanitary Board, Kolar Gold Fields, Champion Reef, in default of which the tender will be rejected.

5. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the contract bond, in default of which his tenders will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the office of the Sanitary Board, Kolar Gold Fields, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders the earnest money on rejected tenders will be returned.

8. Tenders will be opened in public at 4 P.M., on the 6th February 1903, in the office of the Sanitary Board in the Court house at Champion Reef.

9. The first acceptance of any tender will rest with the President, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

Detailed estimate of the probable cost of roofing the platform of Shandi enclosure in Ooregum New Town at Kolar Gold Fields, Bowringpet Taluk, Kolar District.

| Particulars of work. | No. | Dimensions. | | | Contents. | |
|--------------------------------------------------------------------|-----|-------------|-----|------|-----------|------------|
| <i>Earthwork.</i> | | | | | | |
| Excavating foundation for large pillars including partition posts. | 9 | 3½ | 2½ | 3 | 236 | |
| Do small pillars | 18 | 2½ | 1½ | 2½ | 169 | |
| Total | ... | ... | ... | ... | C.ft. 405 | C. yds. 15 |
| <i>Concrete.</i> | | | | | | |
| Around pillars, large | 9 | 3½ | 2½ | 3 | 236 | |
| Do small | 18 | 2½ | 1½ | 2 | 135 | |
| Total | ... | ... | ... | ... | 371 | |
| <i>Deduct.</i> | | | | | | |
| Pillars, large | 9 | 1½ | ½ | 2½ | 17 | |
| Do small | 18 | 1 | ½ | 2 | 18 | |
| Total | ... | ... | ... | ... | 35 | |
| Balance concrete | ... | ... | ... | ... | 336 | C. ft. 336 |
| <i>Burnt stone slabs, dressed</i> | | | | | | |
| Large pillars | 6 | 14 | 1½ | (6") | 126 | |
| Do | 3 | 15½ | 1½ | (6") | 69 | |
| Small pillars | 32 | 8½ | 1 | (6") | 102 | |
| Do | 6 | 9½ | 1 | (6") | 58 | |
| Partition vertical pillars | 32 | 4 | 1 | (6") | 128 | |
| Horizontal slab | 8 | 11½ | 1½ | (4") | 141 | |
| Bed slabs for large pillars | 9 | 2½ | 1½ | (6") | 34 | |
| Do small do | 18 | 2 | 1½ | (6") | 54 | |
| Total burnt stone slabs | ... | ... | ... | ... | 712 | S. ft. 712 |